

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-7

History of original corner establishment:

The corner was originally established by Herman D. Cradon, U. S. Deputy Surveyor, under Contract No. 416, dated August 19, 1881. The original notes state that at the corner position a 3' long by 3" square post was set 24" in the ground, marked $\frac{1}{4}$ S on North face, from which:

A 3" Alder bears N 55° E - 32 links, marked: $\frac{1}{4}$ S BT.

A 36" Pine bears South 75° W - 30 links, marked: $\frac{1}{4}$ S BT.

No other record of corner remonumentation found in County Record.

Description of corner evidence found:

None. Corner area was searched for 3 hours with a 2 man crew, including 3 hours PLS time. The area has been badly disturbed by road construction and logging. Re-established corner by bearing and distance tie from corner 1 of the Medock Quartz Claim MS 225. Corner 1 of the Medock Quartz Claim was re-monumented by Jackson & Prouchnow in 1982. See survey plat. Corner No. 1 of the Medock Quartz Claim bears S 23° 14' 16" W - 611.00'.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 $\frac{1}{2}$ " by 30" aluminum pipe with 2 $\frac{1}{2}$ " aluminum cap, 24" in the ground and surrounded with a mound of earth and stone, from which:

A 14" Western Larch bears N 42 $\frac{1}{2}$ ° E - 123.2', scribed: $\frac{1}{4}$ S5 BT.

A 16" Douglas Fir bears S 72 $\frac{1}{2}$ ° E - 39.0', scribed: $\frac{1}{4}$ S8 BT.


New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-9 and 54-3 to each bearing tree, and painted face of blaze and a 6" red band around each bearing tree.

Set a steel fence post East of corner and attached sign 54-9.


Used steel tape and staff compass with 20° E declination, measured to the center of the bearing trees.

This corner was remonumented on May 12, 1986.

Witnessed by: Willard Hulick.



Willard R. Wells



Cap is Marked:

T10S R36E

1/4 $\frac{S5}{S8}$

1986

PLS 1106

Office of.....County.....Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED June 9, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-55