

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-5

History of original corner establishment:

This corner was originally established by Herman D. Graddon, U.S. Deputy Surveyor, under his Contract No. 416, dated August 19, 1881. The original notes state that at the corner a marked 14 by 12 by 8" basalt stone was set 9" in the ground from which:

A 8" pine bears S80°E-85 lks.
A 24" pine bears N80°W-61 lks.
Both marked $\frac{1}{4}$ S BT.

DIAGRAM

T10S R36E

$\frac{1}{4}$

S18 | S17

In 1974, this corner was recovered and remonumented by Lester E. Fischer, BLM Cadastral Surveyor.

Description of corner evidence found:

Found a 2 $\frac{1}{2}$ " BLM brass cap on a 2" g.i.p. protruding 8" from a mound of earth and stone from which:

A 21" pon. pine bears S80°E-56.0' with healed blaze.
A pine stump bears N75°W-40.3' with no scribing.
A 7" pon. pine bears N83°W-7.8' with open blaze and vis. scribing (BLM bearing tree).

Description of monument and accessories | established to perpetuate the original location of this corner:

Painted face of blaze and a 6" red band around each bearing tree. Attached sign 54-3 and 54-9 to each bearing tree. Set steel fence post North of corner and attached sign 54-9.

Cap is a standard
BLM brass cap marked:

T10S R36E

$\frac{1}{4}$

S18 | S17

1974

Used steel tape and staff compass with 20°E declination. Measured to the center of the bearing trees.

This corner was maintained in May, 1986.

Witness: Bob English.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County Surveyor..... County of...Baker
State of...Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)