

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-13

History of original corner establishment:

This corner was originally established by Herman D. Graddon, U.S. Deputy Surveyor, under his Contract No. 416, dated August 19, 1881. The original notes state that at the corner a marked 18 by 10 by 6" sandstone was set 12" in the ground from which:

DIAGRAM

T10S R36E	
S16	S15
S21	S22

A 10" pine bears N45°E-224 lks, marked T10S R36E S15 BT.
 A 36" pine bears S40°E-70 lks, marked T10S R36E S22 BT.
 A 36" pine bears S20°W-10 lks, marked T10S R36E S21 BT.
 A 12" pine bears N10°W-70 lks, marked T10S R36E S16 BT.

In 1974, this corner was recovered and remonumented by Lester E. Fischer, BLM Cadastral Surveyor.

Description of corner evidence found:

Found a BLM 2½" brass cap on a 2" g.i.p. protruding 6" from a stone mound from which:

A mountain mahogany stump bears N48°E-151.0', with vis. scribing.
 A 32" pon. pine stump bears S38°E-46.2', with no scribing.
 A fallen dead pon. pine bears S20°W-6.6' with vis. scribing.
 A 16" fallen dead pon. pine bears N5°W-46.2' with vis. scribing.
 A 8" pon. pine bears N46°E-147.3' with vis. scribing (BLM BT).
 A 7" pon. pine stump bears S32½°E-41.8' with vis. scribing (BLM BT).
 A 10" pon. pine bears N74°W-27.4' with vis. scribing (BLM BT).

Description of monument and accessories I established to perpetuate the original location of this corner:

From the corner point:

A 7" pon. pine bears S32½°E-40.5' scribed T10S R36E S22 BT.
 A 9" pon. pine bears S20°W-35.0' scribed T10S R36E S21 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is a standard BLM brass cap marked:

T10S R36E	
S16	S15
S21	S22

This corner was maintained in May 1986.

Witness: Bob English.

1974

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of.....County Surveyor.....County of.....Baker
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

GPO-798-276

FILED 9-15-86
 BAKER COUNTY SURVEYOR
 SURVY NO 10-36-59