

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. G-17

History of original corner establishment:

Corner was originally established in 1881,
by Herman D. Gradon, under General Land Office
Contract No. 416. U.S. Surveyor General's Notes
State: Set a post 3-1/2 ft. long 3 ins square
24 ins. in the ground, for 1/4 sec. cor. marked
1/4S on W face,

DIAGRAM

T10S R36E
1/4
S10: S11
1988
PLS 848

from which

A Pine 36 ins. diam bears S53°E. 40 lks dist. marked 1/4 S BT
A pine 30 ins. diam bears S80°W. 34 lks dist. marked 1/4 S BT

Description of corner evidence found:

No trace of the original post remains.
Found two pine stumps which conform reasonably well
with record measure (approx. 3 ft. rad.)
and place the corner near the proportionate position.
However the stumps are high enough that
some scribing should be visible and there is no
assurance that this is the proper position.
Examined all the trees and remains of trees in the
area with no evidence found. There has been logging,
fire and thinning in the area which has destroyed all
traces of the original corner.
Established position at proportionate measure between
the corner found 1/2 mi. North and the corner as
previously set by proportion, 1/2 mi. South.

**Description of monument and accessories established to perpetuate the
original location of this corner:**

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the **DIAGRAM**, SET 22" in the ground.

From Which:

Ponderosa Pine 12" dia., Bears S23°27'E., 5.7 ft., scribed: 1/4 S11 BT

Ponderosa Pine 10" dia., Bears N85°44'W., 37.0 ft., scribed: 1/4 S10 BT

Measurements to trees taken with Electronic Tacheometer with bearings
turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing
Tree Sign above blaze, and warning sign on back of each tree. Painted
a 6" red band at breast ht. around each tree. Set steel fence post with
warning Sign, North, 3 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1998
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Nov. 14, 1988
Refer to Map of Survey No. 10-36-63
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

57 (9/71)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-65