

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. G-19

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
C 1/4
S11
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 23" in the ground.

From Which:

White Fir 10" dia., Bears N35°25'E., 21.5 ft., scribed: C1/4 S11 BT

White Fir 8" dia., Bears N79°28'W., 16.4 ft., scribed: C1/4 S11 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Sign, North 2 ft.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Nov. 14, 1988

Refer to Map of Survey No. 10-36-63

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-66