

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. J-15

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Graddon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 3-1/2 ft. long, 3 ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4 on N face.

DIAGRAM

T10S R36E
S10
1/4-.-
S15
1988
PLS 848

from which

A Pine 16 ins. diam bears N45°E., 11 lks. dist marked 1/4 S BT
A Pine 16 ins. diam bears S30°W., 23 lks. dist. marked 1/4 S BT

Description of corner evidence found:

No trace of the original post is remaining.

Examined all trees, stumps and tree remains in the area. No marks of evidence is found. No trees or remains conform to record measure. Corner is lost to fire, logging and thinning.

Re-established corner at proportionate measure between the corner found 1/2 mi. West and the previously proportioned corner found 1/2 mi. East.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 23" in the ground.

From Which:

Ponderosa Pine 8" dia., Bears N20°14'E., 14.3 ft., scribed: 1/4 S10 BT

Ponderosa Pine 10" dia., Bears S49°02'E., 23.6 ft., scribed: 1/4 S15 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Sign, North 3 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1903
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Nov. 14, 1988

Refer to Map of Survey No. 10-36-63

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-70