

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. J-17

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Gradon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 4 ft. long 4 ins square 24 ins. in the ground, for cor to Secs. 10, 11, 14 & 15, marked. T10S S11 on NE, R36E S14 on SE S15 on SW and S10 on NW faces, with 4 notches on S and 2 notches on E edges,

DIAGRAM

T10S R36E
S10|S11
-.-
S15|S14
1988
PLS 848

From Which

A Pine 40 ins diam bears N50°E., 25 lks. dist. marked T10S R36E S11 BT
A Pine 16 ins diam bears S70°E., 71 lks. dist. marked T10S R36E S14 BT
A Pine 40 ins diam bears S50°W., 23 lks. dist. marked T10S R36E S15 BT
A Pine 30 ins diam bears N35°W., 47 lks. dist. marked T10S R36E S10 BT

Description of corner evidence found:

No trace of the original post is remaining.

Examined all the trees, tree stumps and tree remains in a 100 ft. radius of the search area. There are no marks or evidence found. There are no combination of trees which conform to record. The corner is lost to road construction, logging, mining, fire & thinning. Re-established corner at proportionate measure between the corner found 1 mi. North, 1/2 mi. East, 2 mi. South and 1 mi. West from this position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 23" in the ground.

From Which:

Ponderosa Pine 12"dia., Bears N84°07'W., 8.6 ft., scribed: T10S R36E S10 BT
Ponderosa Pine 14"dia., Bears N52°32'E., 6.4 ft., scribed: T10S R36E S11 BT
Ponderosa Pine 16"dia., Bears S54°43'E., 31.4 ft., scribed: T10S R36E S14 BT
Ponderosa Pine 10"dia., Bears S40°49'W., 27.1 ft., scribed: T10S R36E S15 BT
Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Sign, North 3 ft. from the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1966
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Nov. 14, 1988
Refer to Map of Survey No. 10-36-63
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-71