

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-13

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Gradon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 3 ft. long 3 ins square 24 ins. in the ground for 1/4 sec. cor. marked 1/4 S on W face:

DIAGRAM

T10S R36E
1/4
S21:1S22
1988
PLS 848

from which

A pine 24 ins. diam. bears N20°E. 66 lks. dist marked 1/4 S. BT
A pine 36 ins. diam. bears S75°W. 67 lks dist. marked 1/4 s. BT

Description of corner evidence found:

No trace of the post is remaining.

Examined all stumps, root depressions and remains in the area. There are no marks identifiable and there are no two trees which fit the original record. the area has been logged several times, and a hot fire has gone through the area. There is no trace of the road called 5.25 chains south. The corner is lost to fire and logging and reestablished at proportionate measure between the corner found 1/2 mi. North and the corner as previously set by proportion 1/2 mi. South.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 27" in the ground.

From Which:

Ponderosa Pine 8" dia., Bears N47°42'E., 53.4 ft., scribed: 1/4 S22 BT

Ponderosa Pine 8" dia., Bears N61°27'W., 22.6 ft., scribed: 1/4 S21 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North & South 3 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Sept. 15, 1988

Refer to Map of Survey No. 10-36-62
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-80