

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-4

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
S19
E1/16-. -
S30
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 27" in the ground.

From Which:

A Ponderosa Pine 16" dia., Bears N32°46'W., 11.5 ft., scribed: E1/16 S19 BT

A Ponderosa Pine 10" dia., Bears S 1°20'E., 14.0 ft., scribed: E1/16 S30 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North & South 5 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Nov. 17, 1988

Refer to Map of Survey No. 10-36-64

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-86