

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-5

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Graddon, Under General Land Office Contract No. 416. In 1974, the Bureau of Land Management Remonumented this corner as based on the recovery of original evidence. Such remonumentation is shown in the official BLM Notes, Titled "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS, TOWNSHIP 10 SOUTH, RANGE 36 EAST. Work was executed by: Lester E. Fischer, Cadastral Surveyor, Under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey/Group Number 350, and assignment instructions dated Sept. 13, 1974. The notes to the above described work are referenced and should be viewed as they pertain to this survey.

DIAGRAM

T10S R36E
S 19 1/2 S 20

S 30 1/2 S 29
1974

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM, set in a mound of stone. Corner monument and mound are solid in good condition and need no repair.

Found Bearing Trees as established and described by the Bureau of Land Management, with proper sign as follows:

Ponderosa Pine, 15" dia., bears N80°E., 7.6 ft.
Ponderosa Pine, 12" dia., bears S17°E., 54.1 ft.
Ponderosa Pine, 14" dia., bears S52°W., 22.4 ft.
Ponderosa Pine, 9" dia., bears N19°W., 9.2 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument or mound of stone.

From Which:

Painted a 6" red band at breast ht. around the Bearing Trees as called by BLM.

Proper signs are in place, no other work is needed.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Oct. 17, 1988
Refer to Map of Survey No. 10-36-64
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-87