

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-7

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Graddon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 3 ft. long 3 ins square 24" in the ground, for 1/4 sec. cor. marked 1/4S on N. face:

DIAGRAM

T10S R36E
S20
1/4-.-
S29
1988
PLS 848

from which:

A pine 30 ins. diam bears N50°E., 22 lks dist marked 1/4 S BT
A Pine 24 ins. diam bears S20°W., 46 lks dist marked 1/4 S BT

Description of corner evidence found:

No trace of the original post remaining in this area.
Power line clearing has destroyed all evidence.

Bearing Trees are lost to power line clearing.

Established corner position at proportionate measure between the section corners found 1/2 mi. East and West from this corner.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 27" in the ground.

From Which:

A Fir 16" dia., Bears N20°41'W., 62.1 ft., scribed: 1/4 S20 BT

A Fir 14" dia., Bears S15°46'E., 51.2 ft., scribed: 1/4 S29 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Sign, North 4 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Nov. 21, 1988
Refer to Map of Survey No. 10-36-64
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-88