

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-11

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Gradon, Under General Land Office Contract No. 416. In 1974, the Bureau of Land Management Remonumented this corner as based on the recovery of original evidence. Such remonumentation is shown in the official BLM Notes, Titled "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS, TOWNSHIP 10 SOUTH, RANGE 36 EAST. Work was executed by: Lester E. Fischer, Cadastral Surveyor, Under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey/Group Number 350, and assignment instructions dated Sept. 13, 1974.

DIAGRAM

T10S R36E
S 21
1/4-----
S 28
1974

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM, set solid & vertical in the ground.

Found the Sec. 21 Bearing Tree dead. Found the Sec. 28 Bearing Tree as taken and described by the Bureau of Land Management in good condition, as follows:
Ponderosa pine dead bears N27°W., 7.9 ft.
Ponderosa pine, bears S25°E., 9.6 ft.

Description of monument and accessories established to perpetuate the original location of this corner:

No work is needed at the corner monument.

From Which:

Painted a 6" red band at breast ht. around the Bearing Tree as taken by the Bureau of Land Management.
(New Bearing Tree)
Ponderosa Pine 6" dia., Bears N19°52'E., 7.2 ft., scribed: 1/4 S21 BT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1963
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Sept. 15, 1988
Refer to Map of Survey No. 10-36-62
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-90