

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. S-10

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
NW1/16
S28
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories | established to perpetuate the

original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 27" in the ground.

From Which:

Ponderosa Pine 8" dia., Bears N28°52'W., 46.4 ft., scribed: NW1/16 S28 BT
Ponderosa Pine 18" dia., Bears S11°24'E., 33.6 ft., scribed: NW1/16 S28 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North & West 3 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1938
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Sept. 20, 1988

Refer to Map of Survey No. 10-36-62

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89

BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-99