

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. S-14

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
NW 1/16
S27
1988
PLS 848

Baker County Survey Records show no previous establishment of this Cor.

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 27" in the ground.

From Which:

Ponderosa Pine 8" dia., Bears S83°29'E., 85.9 ft., scribed: NW1/16 S27 BT

Ponderosa Pine 10" dia., Bears N31°56'E., 111.6 ft., scribed: NW1/16 S27 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North 3 ft. & East 4 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1909
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Sept. 27, 1988

Refer to Map of Survey No. 10-36-62

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)