

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-9

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Graddon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 3 ft. long 3 ins square with marked stone, 12 ins in the ground for 1/4 sec. cor. marked 1/4 S on W. face, dug pits 18x18x12 ins. N & S of post, 5-1/2 ft. dist. and raised a mound of earth 1-1/2 ft. high 3-1/2 ft. base around post.

DIAGRAM

T10S R36E
1/4
S291S28
1988
PLS 848

Description of corner evidence found:

The North Fork of the Burnt River has changes course and destroyed all traces of the original post, pits & mound.

There are no accessories originally established. The proportioned position fits the call in the original notes to the North edge of the River bottom (50.00 ch. Leave river bottom). The position is therefore established at proportionate measure between the Section Corners found 1/2 mi. North & South. Note: The relationship between the call to the River and the edge of the River bottom shows the change in the River course. (See the referenced Map)

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET in a 30"x5' mound of stone on the South edge of the North bank of the North Fork of the Burnt River. (River is in a deep cut) From Which:

Set 5/8"x30" iron pins with plastic caps marked PLS 848 and guard posts with Warning and Bearing Tree signs, as follows:

N47°41'W., 16.7 ft., with one notch filed in the top.

N29°09'E., 24.6 ft., pin is not marked.

Measurements to pins taken with Electronic Tacheometer with bearings turned from the survey control network.

The Corner is approx. 3' above the high water level, in a deep cut as formed by the River.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Oct. 11, 1988
Refer to Map of Survey No. 10-36-62
Witnesses: D. Mitchell Ferguson & Ken Deland

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)