

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-15-1/4

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
S27
C-W-W-E
1/256
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 16" in the ground and raised a mound of earth around the pipe.

From Which:

Ponderosa Pine 14" dia., Bears N33°55'W., 38.4 ft., scribed: C-W-W-E 1/256 S27 B
Ponderosa Pine 14" dia., Bears S15°13'E., 43.8 ft., scribed: C-W-W-E 1/256 S27 B
Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, South 5 ft. & West 4 ft. from the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Sept. 26, 1988

Refer to Map of Survey No. 10-36-62

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-114