

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-3

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Gradon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 3 ft. long 3 ins square, 24 ins. in the ground for 1/4 sec. cor, marked 1/4 S on N face.

from which:

A pine 18 ins. diam, bears N65°W., 48 lks dist. marked 1/4 S BT
A pine 18 ins. diam, bears S80°W., 46 lks dist. marked 1/4 S BT

DIAGRAM

T10S R36E
S30
1/4-.-
S31
1988
PLS 848

Description of corner evidence found:

No trace of the original post is remaining

Examined all the trees, stumps and remains of trees in the area. It would seem that with all the well preserved stumps that some marks would be recovered. Gradon had a tendency to scribe high and this must be the case. There are more than one combination which would conform reasonably well to record measure. Corner is determined to be lost and reestablished at proportionate measure between the section corners found 1/2 mi. East and West from this position.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 24" in the ground.

From Which:

Ponderosa Pine 7" dia., Bears N21°40'W., 27.6 ft., scribed: 1/4 S30 BT

Ponderosa Pine 7" dia., Bears S54°46'W., 11.9 ft., scribed: 1/4 S31 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Signs, North 3 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1908
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Nov. 19, 1988

Refer to Map of Survey No. 10-36-64

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-123