

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-7

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Gradon, Under General Land Office Contract No. 416. In 1974, the Bureau of Land Management Remonumented this corner as based on the recovery of original evidence. Such remonumentation is shown in the official BLM Notes, Titled "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS, TOWNSHIP 10 SOUTH, RANGE 36 EAST. Work was executed by: Lester E. Fischer, Cadastral Surveyor, Under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey/Group Number 350, and assignment instructions dated Sept. 13, 1974. The notes to the above described work are referenced and should be viewed as they pertain to this survey.

DIAGRAM

T10S R36E
S29
1/4-----
S32
1974

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM, set solid and plumb with brass cap 6" above ground. No repair needed.

Found Bearing Trees as established and described by the Bureau of Land Management, with proper signs as follows:

Original Bearing Tree, a Western Larch 18" dia., bears N60°E., 9.2 ft.

New Bearing Tree, a Ponderosa Pine 11 " dia., Bears S67°W., 32.7 ft.

Description of monument and accessories | established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

Painted a 6" red band at breast ht. around the Bearing Trees as called by BLM.

Proper signs are in place, no other work is needed.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1929
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Nov. 10, 1988
Refer to Map of Survey No. 10-36-64
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-125