

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-9

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Gradon, Under General Land Office Contract No. 416. In 1974, the Bureau of Land Management Remonumented this corner as based on the recovery of original evidence. Such remonumentation is shown in the official BLM Notes, Titled: "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS, TOWNSHIP 10 SOUTH, RANGE 36 EAST. Work was executed by: Lester E. Fischer, Cadastral Surveyor, Under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey/Group Number 350, and assignment instructions dated Sept. 13, 1974.

DIAGRAM

T10S R36E
S 291S 28

S 321S 33
1974

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM, set in a mound of stone. Corner monument and mound are solid in good condition and need no repair.

Found Bearing Tree as established and described by the Bureau of Land Management, with proper sign as follows:

Western Larch , 10" dia., bears N73°E., 22.1 ft.
Ponderosa Pine, dead, bears S 3°E., 11.2 ft.
Ponderosa Pine, dead, bears S52°W., 17.5 ft.
No tree in the NW quadrant, BLM record calls for a lodgepole pine 8" dia., bears N72°W., 14.2 ft.

Description of monument and accessories | established to perpetuate the original location of this corner:

No work is needed on the monument or mound of stone.

From Which:

New bearing Trees, taken in this survey:

Western Larch 8" dia., Bears S79°57'E., 38.6 ft., scribed: T10S R36E S33 BT
Western Larch 10" dia., Bears S57°01'W., 38.8 ft., scribed: T10S R36E S32 BT
White Fir 8" dia., Bears N20°25'W., 32.7 ft., scribed: T10S R36E S29 BT

Measurements to new trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each new tree. Painted a 6" red band at breast ht. around all trees.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Sept. 23, 1988

Refer to Map of Survey No. 10-36-64

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-126