

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-13

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Graddon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 4 ft. long 4 ins square with marked stone, 12 ins in the ground for Cor. to Sections, 27,28,33 & 34 marked T10S S27 on NE R36E, S34 on SE, S33 on SW and S28 on NW faces,

DIAGRAM

T10S R36E
S28 S27
-.-
S33 S34
1988
PLS 848

with 1 notch on S & 3 notches on E edges, dug pits 18x18x12 ins in each sec. 5 1/2 ft. dist and raised a mound of earth 2 ft. high 4-1/2 ft. base around post.

Description of corner evidence found:

No trace of the original post, pits or mounds is remaining at this location near the River.

There are no accessories originally established. There are topography calls to the river South & West from the corner. The River shows signs of having changed course over the years and the topog calls provide a position which would distort the adjacent sections. Established corner position at proportionate measure between the nearest corners found 2 mi. North, 1 mi. East, 1 mi. South and 1/2 mi. West.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground.

From Which:

Set 5/8"x30" iron pins, with plastic caps stamped PLS 848, and guard posts (Warning and Bearing Tree signs, as follows: N45°00'W., 10.0 ft; N45°E., 10.0 ft; S45°E., 10.0 ft; and S45°., 10.0 ft from the pipe.

Measurements to pins taken with Electronic Tacheometer with bearings turned from the survey control network.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1960
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Sept. 12, 1988

Refer to Map of Survey No. 10-36-61

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19....

..... by

(COUNTY OFFICIAL)

(DEPUTY)