

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-17

History of original corner establishment:

Corner was originally established in 1881,
by Herman D. Gradon, under General Land Office
Contract No. 416. U.S. Surveyor General's Notes
State: Set a post 4 ft. long 4 ins square, 24"
in the ground, for Cor. to Secs. 26,27,34 & 35
marked. T10S S26 on NE
R37E S35 on SE
S34 on SW and S27 on NW faces, with 1 notch on
S and 2 notches on E edges.
From which

A pine 48 ins. diam bears S80°W 237 lks. dist. marked T10S R36E S34 BT
A pine 44 ins. diam bears N70°W 185 lks. dist. marked T10S R36E S27 BT
No other trees within limits and raised a mound of stone alongside.

DIAGRAM

T10S R36E
S27:S26
-.-
S34:S35
1988
PLS. 848

Description of corner evidence found:

Found a mound of stone. PLS 645 J.Hambilton states
that in 1966, the remains of both trees are here and
the mound is in the proper position, in relation to
the trees.

Found the remains of a stump, which has been cut off
at ground level N67°W (Mag Compass with 20°
East Dec.), 123.0 ft. from the center of the mound of
stone. [Record N70°W., 122.1 ft.] The other Tree
falls in the road bed of Hwy. 7.

The Position of the center of the above described stone
mound conforms to surrounding measurements and is
therefore accepted as the Section Corner.

**Description of monument and accessories I established to perpetuate the
original location of this corner:**

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the **DIAGRAM**, SET 16" in the ground and reconstructed the stone mound
around the pipe.

From Which:

Ponderosa Pine 20" dia., Bears N81°36'W., 142.8ft., scribed: T10S R36E S27 BT
Ponderosa Pine 18" dia., Bears N56°56'E., 129.6ft., scribed: T10S R36E S26 BT
Ponderosa Pine 20" dia., Bears S49°36'E., 74.2ft., scribed: T10S R36E S35 BT
Ponderosa Pine 22" dia., Bears S19°52'W., 169.8ft., scribed: T10S R36E S34 BT
Measurements to trees taken with Electronic Tacheometer with bearings
turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing
Tree Sign above blaze, and warning sign on back of each tree. Painted
a 6" red band at breast ht. around each tree. Set steel fence post with
warning Sign, North 3 ft. from the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1983
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Sept 13, 1988
Refer to Map of Survey No. 10-36-61
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-132