

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. W-11

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
C
N1/161S33
C
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories I established to perpetuate the

original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground.

From Which:

Western Larch 12"dia., Bears S33°36'W., 53.3ft., scribed: C-N 1/16 S33 BT

Lodgepole Pine 8"dia., Bears N38°17'E., 50.0ft., scribed: C-N 1/16 S33 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, South & West 3 ft. from the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1963
DOUGLAS M. FERGUSON
848**

This work is performed by:

Douglas M. Ferguson PLS 848

Mt. Vernon Oregon.

On: Sept. 13, 1988

Refer to Map of Survey No. 10-36-61

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

GPO-791-311

FILED 3-30-89

BAKER COUNTY SURVEYOR

SURVEY NO. 10-36-135