

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-11

**History of original corner establishment:**

Baker County Survey Records show no previous establishment of this Cor.

**DIAGRAM**

T10S R36E  
C 1/4  
S33  
1988  
PLS 848

**Description of corner evidence found:**

Baker County Survey Records show no previous establishment of this Cor.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 10" in the ground and raised a mound of stone around the pipe.

From Which:

Ponderosa Pine 6"dia., Bears N 9°28'E., 14.8ft., scribed: C1/4 S33 BT

Ponderosa Pine 6"dia., Bears S63°26'W., 7.8ft., scribed: C1/4 S33 BT

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Sign, North 4 ft. from the corner.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1969  
DOUGLAS M. FERGUSON  
848

This work is performed by:  
Douglas M. Ferguson PLS 848  
Mt. Vernon Oregon.

On: Sept. 14, 1988

Refer to Map of Survey No. 10-36-61

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)