

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-11&1/2

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
C-W-E
1/64
S33
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 28" in the ground.

From Which:

Ponderosa Pine 12" dia., Bears S57°54'W., 39.6ft. scribed: C-W-E1/64 S33 BT
Lodgepole Pine 8" dia., Bears N37°57'W., 19.0ft. scribed: C-W-E1/64 S33 BT
Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North 9 ft. & East 4 ft. from the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1965
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Sept. 13, 1988
Refer to Map of Survey No. 10-36-61
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)