

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-13

History of original corner establishment:

Corner was originally established in 1881, by Herman D. Graddon, under General Land Office Contract No. 416. U.S. Surveyor General's Notes State: Set a post 3-1/2 ft. long, 3 ins. square with marked stone, 12 ins. in the ground, for 1/4 sec. cor. marked 1/4 S on W face, dug pits, 18x18x12 ins. N & S of post 5-1/2 ft, dist, and raised a mound of earth 1-1/2 ft. high, 3-1/2 ft, base, around post.

DIAGRAM

T10S R36E
1/4
S331S34
1988
PLS 848

Description of corner evidence found:

There is no trace of the post, pits or mound in this cultivated hay field.

There are no accessories originally established. There are no topography calls which will provide any better fix on the position than at midpoint between section corners. Determined the corner to be lost and reestablished at proportionate measure between the corner as previously set at proportionate measure 1/2 mi. North and the section corner found 1/2 mi. South.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground.

From Which:

Set 5/8"x30" iron pins with plastic caps stamped: PLS 848, and guard posts with Warning, Bearing Tree, and Boundary Signs as follows:

N89°57'W., on the property line, 10.1 ft.

S 0°10'W., " " " " , 10.1 ft.

Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.



This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Sept. 12, 1988
Refer to Map of Survey No. 10-36-61
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)