

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-15

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.

DIAGRAM

T10S R36E
C 1/4
S34
1988
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 29" in the ground.

From Which:

Set 5/8"x30" iron pins with plastic caps stamped: PLS 848, and guard posts with Warning and Bearing Tree Signs as follows:

N10°30'E., 31.5 ft, in County Road Right of Way fence.

S85°05'E., 31.6 ft, in County Road Right of Way fence.

Measurements to pins taken with Electronic Tacheometer with bearings turned from the survey control network.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1998
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.

On: Sept. 8, 1988

Refer to Map of Survey No. 10-36-61

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-144