

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-16

**History of original corner establishment:**

Baker County Survey Records show no previous establishment of this Cor.

**DIAGRAM**

T10S R36E  
E1/16  
C-.-C  
S34  
1988  
PLS 848

**Description of corner evidence found:**

Baker County Survey Records show no previous establishment of this Cor.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 24" in the ground.

From Which:

Set 5/8"x30" iron pins with plastic caps, stamped PLS 848 and guard posts with warning and Bearing Tree signs, as follows:

S 0°20'W, on property line, 10.0 ft.

S89°47'W, on property line, 10.0 ft.

Measurements to pins taken with Electronic Tacheometer with bearings turned from the survey control network.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1988  
DOUGLAS M. FERGUSON  
848

This work is performed by:  
Douglas M. Ferguson PLS 848  
Mt. Vernon Oregon.

On: Sept. 8, 1988

Refer to Map of Survey No. 10-36-61

Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89  
BAKER COUNTY SURVEYOR  
SURVEY NO. 10-36-146