

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. Z-17

History of original corner establishment:

Corner was originally established in 1881, by Eugene P. McCornack, Under General Land Office Contract No. 398. In 1974, the Bureau of Land Management Remonumented this corner as based on the recovery of original evidence. Such remonumentation is shown in the official BLM Notes, Titled "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS, TOWNSHIP 10 SOUTH, RANGE 36 EAST. Work was executed by: Lester E. Fischer, Cadastral Surveyor, Under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey/Group Number 350, and assignment instructions dated Sept. 13, 1974.

DIAGRAM

SC
T10S R36E
S34!S35

1974

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM, set in a poorly constructed and deteriorating mound of stone.

Found Bearing Trees as established and described by the Bureau of Land Management, in poor condition, dead or dying.

Description of monument and accessories I established to perpetuate the original location of this corner:

(New Bearing Trees)

Lodgepole Pine 10" dia., Bears N50°30'W., 43.7ft., scribed: T10S R36E S34 BT
Ponderosa Pine 10" dia., Bears N80°25'E., 25.4ft., scribed: T10S R36E S35 BT
Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North & West 6 ft. from the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1999
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Sept. 1, 1988
Refer to Map of Survey No. 10-36-61
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 10-36-158