

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously set.

DIAGRAM

T10S R37E

W 1/16 $\frac{\text{S4}}{\text{S9}}$

**1994
PLS699**

Description of corner evidence found:

Corner is being set by this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2" aluminum pipe with 3 1/4" aluminum cap, stamped as shown in diagram, 26" in ground, at a point as determined by the procedures set forth in the MANUAL OF INSTRUCTIONS FOR THE SURVEY OF PUBLIC LANDS for the subdivision of sections, from which new accessories are:

A 10" Ponderosa Pine, bears N71°35'E, 25.43 ft., scribed "W1/16 S16 BT"

A 12" Ponderosa Pine, bears S0°30'E, 14.40 ft., scribed "W1/16 S9 BT"

Also set galvanized steel posts with "Property Boundary" and "Land Survey Monument" sign 3 ft. W. and "Property Boundary" sign 3 ft. N..


I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 15, 1994, I monumented the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS
7 DAY OF Feb, 1995.

10-37-57

Baker County Surveyor

Client: US Forest Service



Renewal Date 1/1/97

T10S R37E J-10