

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a post 4 ft long 4 ins square 24 ins in the ground, for cor. to secs 10,11,14&15, marked T10S S11 on NE; R37E S14 on SE; S15 on SW; and S10 on NW faces with 4 notches on S and 2 notches on E edges from which:

- A pine 10 ins diam. bears S40°E, 29 lks dist, marked T10S R37E S14 BT.
- A pine 12 ins diam. bears S60°W, 29 lks dist, marked T10S R37E S15 BT.
- A pine 12 ins diam. bears N60°W, 19 lks dist, marked T10S R37E S10 BT.
- No other tree within limits and dug a pit 18x18x12 ins. in Sec 11."

DIAGRAM

T10S R37E

S10 | S11

S15 | S14

1982
ORLS 1898

In 1982, Harry Hildebrand, PLS 1898, monumented the corner as follows:

"At the corner location I found a 1" iron pipe set but no filing made. I also, when digging the hole for the brass cap, found pieces of the original wooden post.

The N60°W BT is a 38" stump 15.6 ft. marked E S10

The S40°E BT is a 26" stump 19.5 ft. marked S14.

The SW BT is gone due to road construction.

I could not discern the pit that was set in Sec 11.

I set a 2½"x32" brass capped steel pipe in the original position 26" in the ground in a mound of stone from which

A 15" Ponderosa Pine bears S43°E 18.65 ft. marked T10S R37E S14 BT Nail in NE base.

The corner is 13 ft. South of 4-strand barb wire fence.

No other bearing trees or objects available.

Bearings taken with a staff compass. Declination set 18½°E. per 1980 Isogonic chart. Distances pulled to 60d nails with a brass washer marked LS 1898 set in side center of bearing trees."

Description of corner evidence found:

Found 1982 PLS 1898 brass cap in good condition, stamped as shown on diagram, with steel post set 4 ft. NE, from which:

A 17" Ponderosa Pine in good condition bears S44°30'E, 18.65 ft., with scribing visible.

A 46" Ponderosa Pine stump 36" high bears N62°W, 15.4 ft., with scribing visible.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained corner by attaching "Land Survey Monument" signs to steel post and bearing trees as needed, painting 6" wide red bands around bearing trees, and making new accessories:

A 17" Ponderosa Pine bears N60°50'W, 135.8 feet scribed T10S R37E S10 BT

A 13" Ponderosa Pine bears S61°40'W, 95.4 feet scribed T10S R37E S15 BT

A 20" Ponderosa Pine bears N82°40'E, 46.0 feet scribed T10S R37E S11 BT

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on July 11, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-61

Baker County Surveyor

Client: Lyle Defrees & US Forest Service

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 9, 1985
LELAND LEE MYERS
699

Renewal Date 1/1/97

T10S R37E J-17