

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a basalt stone 18 x 10 x 7 ins. 12 ins in the ground, for 1/4 sec. cor., marked 1/4 on W. face, from which

A pine 16 ins diam. bears S70°E, 75 lks. dist., marked 1/4 S BT.

A pine 15 ins diam. bears N80°W, 96 lks. dist., marked 1/4 S BT."

In 1971 the Bureau of Land Management monumented the corner as follows:

"The 1/4 sec. cor. of secs. 25 and 26, monumented with the original basalt stone, 18 x 10 x 7 ins., firmly set 12 ins. in the ground, mkd 1/4 on W. face, from which the remains of the original bearing trees:

A pine stump, 18 ins. diam., bears S80°E, 78 lks. dist., with scribe marks BT visible on open blaze.(Record, S70°E, 75 lks)

A pine, 20 ins. diam., bears N70°W, 99 lks. dist., with scribe marks BT visible on open blaze.(Record, N80°W, 96 lks.)

At the corner point set an iron post 28 ins. long, 2 1/2 ins, diam., 18 ins. in the ground, to bedrock supported in a collar of stone, 4 ft. base, to top, with brass cap mkd. as shown on diagram, from which new bearing trees:

A ponderosa pine, 10 ins. diam., bears S83°E, 42 lks. dist., mkd. 1/4 S25 BT.

A ponderosa pine, 10 ins. diam., bears S87°W, 15 1/2 lks. dist., mkd 1/4 S26 BT.

Bury corner stone alongside iron post.

The corner is located under a fence line, extending North and South."

DIAGRAM

T10S R37E

1/4

S26 | S25

**1971
BLM**

Description of corner evidence found:

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post set alongside, from which:

An 11" Ponderosa Pine, bears S83°E, 42 lks., with blaze healed over.

An 11" Ponderosa Pine, bears S87°W, 15 1/2 lks., with blaze healed over.

Description of monument and accessories I established to perpetuate the original location of this corner:

new accessories are:

A silver DEEP (Underground Magnetic Locator), bears North, 3.10 ft. from corner position, 0.9 ft. in ground.

A blue DEEP, bears South, 5.75 ft. from corner position, 0.7 ft. in ground.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on November 19, 1994, I maintained the corner as herein described.


FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-70

Baker County Surveyor

Client: Lyle Defrees & US Forest Service



Renewal Date 1/1/97

T10S R37E T-21