

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a granite stone 20 x 10 x 4 ins. 15 ins in the ground, for 1/4 sec. cor., marked 1/4 on W. face, from which

A pine 8 ins diam. bears S60°E, 13 lks. dist., marked 1/4 S BT.

A fir 15 ins diam. bears N60°W, 46 lks. dist., marked 1/4 S BT."

In 1971 the Bureau of Land Management monumented the corner as follows:

"The 1/4 sec. cor. of secs. 35 and 36, monumented with the original granite stone, 20 x 10 x 4 ins., firmly set 12 ins. in the ground, and in a mound of stone, 3 1/2 ft. base, 8 ins. high, mkd 1/4 on W. face, from which the remains of the original bearing trees:

A fir, 18 ins. diam., bears N62°W, 46 lks. dist., with scribe marks 1/4 S BT visible on open blaze. (Record, N60°W)

At the corner point set an iron post 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, to bedrock supported in a collar of stone, 3 1/2 ft. base, to top, with brass cap mkd. as shown on diagram, from which new bearing trees:

A western larch, 9 ins. diam., bears S32°E, 110 lks. dist., mkd. 1/4 S36 BT.

A ponderosa pine, 14 ins. diam., bears N27°W, 39 lks. dist., mkd 1/4 S35 BT.

Bury corner stone alongside iron post.

Description of corner evidence found:

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post set alongside.

18" Ponderosa Pine in good condition, with blaze healed over, bears N27°W, 25.7 feet.

10" Western Larch in good condition, with blaze healed over, bears S32°E, 72.6 feet.

Did not look for the original BTs.

DIAGRAM

T10S R37E

1/4

S35

S36

1971

BLM

Description of monument and accessories I established to perpetuate the original location of this corner:

Added new accessories which are:

A silver DEEP (Underground Magnetic Locator), bears North, 3.6 ft. from corner position, 0.6 ft. in ground.

A blue DEEP, bears South, 3.6 ft. from corner position, 1.0 ft. in ground.

Attached BT, as needed, and Land Survey Monument signs to and painted a red band around each BT. Used the 1971 record bearing and distance for the BTs. Set steel fence posts 5 feet East and 5 feet North of the corner on the National Forest boundary lines. Attached Forest Boundary signs to each post and a Land Survey Monument sign on the East post.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on November 20, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS
7 DAY OF Feb, 1995.

10-37-74

Baker County Surveyor

Lyle Defrees & US Forest Service

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 9, 1985
LELAND LEE MYERS
699

Renewal Date 1/1/97

T10S R37E X-21