

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Grandon, U.S. Deputy Surveyor
July 1, 1882

39.12 Set a basalt stone 12 x 8 x 5 ins., 8 ins in the ground for the $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which:

A pine, 28 ins. diam., bears N.35°W., 27 lks. dist., mkd. $\frac{1}{4}$ SBT.
A pine, 6 ins. diam., bears S.50°W., 54 lks. dist., mkd. $\frac{1}{4}$ SBT.

DIAGRAM
T 10 S R 37 E

S 5
 $\frac{1}{4}$ -----
S 8

1971

Owen C. Chatters, II, and Lester E. Fischer, Cadastral Surveyors
July 26, 1974

The $\frac{1}{4}$ sec. cor. of secs. 5 and 8, monumented with a mound of stone, 2 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A pine stump, 30 ins. diam., bears N.35°W., 27 lks. dist., no marks visible.

A pine, 18 ins. diam., bears S.50°W., 54 lks. dist., with scribe marks $\frac{1}{4}$ S BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2 $\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A fir, 11 ins. diam., bears N.5°E., 53 lks. dist., mkd. $\frac{1}{4}$ S5 BT.

A ponderosa pine, 10 ins. diam., bears S.54 $\frac{1}{2}$ °W., 69 lks. dist., mkd. $\frac{1}{4}$ S8 BT.

Bury a basalt stone, 12 x 8 x 4 ins., with an X chiseled on N. face, alongside iron post, and raise a mound of stone, 2 ft. base, 1 $\frac{1}{2}$ ft. high, N. of the corner.

Description of corner evidence found:

Found a 3" BLM brass cap, 0.2' above the ground with mound of stones to the north, from which:

A stump, with BT sign, bears N.37°30'W., 20'.

A fir, 13" diam., bears N.13°20'E., 35', with healed blaze.

A pine, 19" diam., bears S.4°14'W., 35.6', with healed blaze.

A pine, 12" diam., bears S.50°36'W., 44.8', with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-81