

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not perviously set.

DIAGRAM
T 10 S R 37 E
C ¼ S 17
RLS 1060
1995

Description of corner evidence found:

Corner is being set this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the point, determined by the procedures in the MANUAL OF INSTRUCTION FOR THE SURVEY OF PUBLIC LANDS , set a USFS 3¼" aluminum capped monument 16" in the ground, with a 3' mound of stone to cap, from which:

A fir, 6" in diam., bears S.78°45'W., 6.2 ft., double blazed and scribed "C¼S17BT" with nail and brass washer "RLS 1060", on face of blaze.
A fir, 11" in diam., bears N.50°20'W., 6.9 ft., double blazed and scribed "C¼S17BT" with nail and brass washer "RLS 1060", on face of blaze.
A tamarack, 8" in diam., bears S.8°50'W., 7.8 ft., double blazed and scribed "C¼S17BT" with nail and brass washer "RLS 1060", on face of blaze.
A tamarack, 10" in diam., bears N.78°45'E., 21.0 ft., double blazed and scribed "C¼S17BT" with nail and brass washer "RLS 1060", on face of blaze.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1080

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

L-7

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-102