

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously set.

DIAGRAM

1

SE -- S17
16

RLS 1060
1995

Description of corner evidence found:

Corner is being set this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the point, determined by the procedures in the MANUAL OF INSTRUCTION FOR THE SURVEY OF PUBLIC LANDS, set a USFS 3 1/4" aluminum capped monument 18" in the ground, with a 4' mound of stone to cap, from which:

A fir, 12" in diam., bears S1.40°W., 6.6 ft., double blazed and scribed "SE1/16S17BT" with nail and brass washer "RLS 1060", on face of blaze.

A fir, 7" in diam., bears N.64°W., 3.3 ft., double blazed and scribed "SE1/16S17BT" with nail and brass washer "RLS 1060", on face of blaze.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____

State of _____ I hereby certify that the within instrument was filed in this office for record on the ____ day of _____, 19__

_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

M-8

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-108