

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously set.

DIAGRAM

1
SE -- S 15
16

RLS 1060
1995

Description of corner evidence found:

Corner is being set this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the point, determined by the procedures in the MANUAL OF INSTRUCTION FOR THE SURVEY OF PUBLIC LANDS, set a USFS 3¼" aluminum capped monument 7" in the ground, with a mound of stone to cap.

A pine, 6" in diam., bears N.12°W., 21.2 ft., double blazed and scribed "SE1/16S15BT"

with nail and brass washer "RLS 1060", on face of blaze.

A pine, 6" in diam., bears N.82°30'W., 28.8 ft., double blazed and scribed "SE1/16S15BT" with nail and brass washer "RLS 1060", on face of blaze.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

M-16

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-111