

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

80.00 Set a post 4 ft. long 4 ins square, 24 ins in the ground, for cor.
to secs 15, 16, 21, 22, marked

T10S S15 on N.E.
R37E S22 on S.E.
S21 on S.W. and
S16 on N.W. faces with 3 notches on S and E. edges, from which:

A tamarack, 5 ins. diam., bears N.65°E., 39 lks. dist., mkd. T10S R37E S15 BT.
A pine, 36 ins. diam., bears S.80°E., 74 lks. dist., mkd. T10S R37E S22 BT.
A pine, 40 ins. diam., bears S.50°W., 34 lks. dist., mkd. T10S R37E S21 BT.
A tamarack, 15 ins. diam., bears N.60°W., 87 lks. dist., mkd. T10S R37E S16 BT.

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The cor. of secs. 15, 16, 21, and 22, monumented with the original pine post, 4 ft. long, 4 ins. square, firmly set, projecting 18 ins. above the ground, with illegible scribe marks on all four sides, from which the remains of the original bearing trees:

A western larch, 17 ins. diam., bears N.65°E., 39 lks. dist., with scribe marks T10S R37E S15 BT visible on opened blaze.
A pine, 40 ins. diam., bears S.80°E., 78 lks. dist., with healed blaze. (Record, 74 lks.)
A pine stump, 40 ins. diam., bears S.50°W., 34 lks. dist., no marks visible.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A fir, 15 ins. diam., bears N.7°E., 27½ lks. dist., mkd. T10S R37E S15 BT.
A fir, 6 ins. diam., bears S.40°E., 37½ lks. dist., mkd. T10S R37E S22 BT.
A ponderosa pine, 8 ins. diam., bears S.48°W., 66 lks. dist., mkd. T10S R37E S21 BT.
No other trees available within limits.
Reset corner post alongside iron post.

Description of corner evidence found:

Found a 3" diam. BLM brass cap, 0.1' above the ground with a "T" post alongside, from which:

A fir, 20" in diam., bears N.6°15'E., 17.8', with a healed blaze.
A dead tree, 14" in diam., bears N.64°41'E., 26.9', scribe visible.
A pine, 38" in diam., bears S.79°53'E., 51.2', with a healed blaze.
A fir, 8" in diam., bears S.41°16'E., 24.3', with a healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

A fir, 7" in diam., bears S.26°07'W., 9.5 ft., double blazed and scribed "T10SR37ES21BT" with nail and brass washer "RLS 1060", on face of blaze.

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

N-13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-113