

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

80.00 Set a basalt stone 18 x 12 x 10 ins., 12 ins in the ground for the cor. to secs. 14, 15, 22, and 23, marked with 3 notches on S., and 2 notches on E. edges, from which:

A pine, 40 ins. diam., bears N.65°E., 38 lks. dist., mkd. T10S R37E S14 BT.

A pine, 28 ins. diam., bears S.25°E., 96 lks. dist., mkd. T10S R37E S23 BT.

A pine, 24 ins. diam., bears S.40°W., 52 lks. dist., mkd. T10S R37E S22 BT.

A pine, 44 ins. diam., bears N.25°W., 96 lks. dist., mkd. T10S R37E S15 BT.

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The cor. of secs. 14, 15, 22, and 23, perpetuated by person(s) unknown, monumented with an iron pipe, 2½ ins. diam., projecting 12 ins. above the ground, with a mound of stone, 2 ft. base, 1½ ft. high, N. of corner, alongside of which is the original basalt stone, 18 x 10 x 5 ins., firmly set 12 ins. in the ground, mkd. with 3 grooves on S. face and 2 grooves on E. face, from which the remains of the original bearing trees:

A root hole, bears N.65°E., 38 lks. dist., with a decayed pine alongside, size indeterminate, no marks visible.

A pine stump, 30 ins. diam., bears S.22°E., 96 lks. dist., with scribe marks BT visible on open blaze. (record S.25° E.)

A pine, 28 ins. diam., bears S.42°W., 52 lks. dist., with healed blaze. (record, S. 40° W.)

A pine stump, 48 ins. diam., bears N.25°W., 96 lks. dist., with scribe marks BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 12 ins. in the ground, to bed rock, supported in a collar of stone, 4 ft. base, to top, with brass cap, from which new bearing trees:

A ponderosa pine, 10 ins. diam., bears N.65°E., 50 lks. dist., mkd. T10S R37E S14 BT.

A ponderosa pine, 10 ins. diam., bears S.51°E., 82 lks. dist., mkd. T10S R37E S23 BT.

A ponderosa pine, 8 ins. diam., bears S.61°W., 122 lks. dist., mkd. T10S R37E S22 BT.

A ponderosa pine, 8 ins. diam., bears N.49°W., 9 lks. dist., mkd. T10S R37E S15 BT.

Bury corner stone and reset iron pipe alongside iron post.

Description of corner evidence found:

Found a 3" diam. BLM brass cap, 18" above the ground in a 5' mound of stone. (a 2.5" threaded pipe sits 9" to the north-east), from which:

A pine, 10" in diam., bears N.49°W., 5.5', with a healed blaze.

A pine, 10" in diam., bears N.64°59'E., 33.4', with a healed blaze.

A pine, 13" in diam., bears S.51°26'E., 54.7', with a healed blaze.

A pine, 28" in diam., bears S.40°32'W., 35.7', with a healed blaze.

A pine, 10" in diam., bears S.56°55'W., 79.1', with a healed blaze.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Description of monument and accessories I established to perpetuate the original location of this corner:

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

N-17

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-116