

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

80.00 Set a post 4 ft. long 4 ins. square 24 ins. in the ground, for cor. to secs. 22, 23, 26, and 27, marked with 2 notches on S and E. edges, from which:

- A pine, 16 ins. diam., bears N.40°E., 36 lks. dist., mkd. T10S R37E S23 BT.
- A pine, 18 ins. diam., bears S.25°E., 8 lks. dist., mkd. T10S R37E S26 BT.
- A fir, 18 ins. diam., bears S.40°W., 58 lks. dist., mkd. T10S R37E S27 BT.
- A tamarack, 14 ins. diam., bears N.40°W., 52 lks. dist., mkd. T10S R37E S22 BT.

DIAGRAM
T 10 S R 37 E

S 22 | S 23

S 27 | S 26

1971

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The cor. of secs. 22, 23, 26, and 27 perpetuated by person(s) unknown, monumented with an iron pipe, 2½ ins. diam., projecting 8 ins. above the ground, from which the remains of the original bearing trees:

- A pine stump, 18 ins. diam., bears N.44°E., 36 lks. dist., with scribe marks BT visible on open blaze. (record N.40°E)
- A pine stump, 20 ins. diam., bears S.25°E., 8 lks. dist., with scribe marks BT visible on open blaze.
- A root hole, bears S.40°W., 58 lks. dist., with a down fir alongside, size indeterminate, no marks visible.
- A western larch snag, 16 ins. diam., bears N.40°W., lks. dist., mkd. T10S R37E S22 BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

- A ponderosa pine, 11 ins. diam., bears N.7°E., 73½ lks. dist., mkd. T10S R37E S23 BT.
- A western larch, 12 ins. diam., bears S.68°E., 115 lks. dist., mkd. T10S R37E S26 BT.
- A western larch, 11 ins. diam., bears S.14°W., 33 lks. dist., mkd. T10S R37E S27 BT.
- A ponderosa pine, 7 ins. diam., bears N.38°W., 46 lks. dist., mkd. T10S R37E S22 BT.
- Bury a basalt stone, 4 x 4 x 3 ins., with an X chiseled on W. face and reset the iron pipe alongside iron post.

Leland Lee Myres, RLS 699
1995

Found 1971 BLM brass cap in good condition, stamped as shown in diagram, with steel post set 4 ft. NE, from which:

- A 14" western larch bears S68°E., 115 lks., with blaze healed over.
- A 13" western larch bears S14°W., 33 lks., with blaze healed over.

Maintained corner by attaching "Land Surveying Monument" sign to steel post and bearing trees as needed, painted 6" wide red bands around bearing trees, and making new accessories:

- A 14" western larch, bears N61°30'W, 25.19 ft., scribed T10SR37ES22BT.
- A 9" western larch, bears N7°10'E, 37.76 ft., scribed T10SR37ES23BT.

Description of corner evidence found:

Found a BLM brass cap, 0.3' above the ground with no stones, from which:

- A tamarack, 15" diam., bears S.9°55'W., 21.7', with healed blaze.
- A tamarack, 12" diam., bears N.61°23'W., 25.2', scribed "T10SR37ES22BT".
- A tamarack, 8" diam., bears N.6°11'E., 37.8', scribed "T10SR37ES23BT", with nail and washer "PLS 699".
- A tamarack, 16" diam., bears S.71°30'E., 75.3', with healed blaze, and a nail on side.

Description of monument and accessories I established to perpetuate the original location of this corner:

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

R-17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-118