

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Eugene P. McCornack, U.S. Deputy Surveyor
July 27, 1881

80.00 Set a post 4 ft. long, 4 ins. square, 24 ins in the ground for standard cor. to Tps.
10S R37 and 38E marked
SCT10S on N.,
R38ES31 on E., and
R37ES36 on W. faces with 6 notches on N.E. and W. faces. From which:

A pine, 24 ins. diam., bears N.50°E., 55 lks. dist. mkd. T10SR38ES31BT.
A fir, 30 ins. diam., bears N.55°W., 26 lks. dist. mkd. T10SR37ES36BT.
A fir, 24 ins. diam., bears S.10°W., 19 lks. dist. mkd. T11SR37ES1BT.

Owen C. Chatters II and James J. Carlson, Cadastral Surveyors
June 15, 1971

The standard cor. of Tps. 10S., Rs.37 and 38 E., determined at record bearing and distance from the remains of the original bearing trees:

A pine stump, 28 ins. diam., bears N.50°E., 55 lks. dist. with scribe marks BT visible on open blaze.
A fir stump, 32 ins. diam., bears N.55°W., 26 lks. dist., with scribe marks BT visible on open blaze.

At the corner point:

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap,

from which new bearing trees:

A larch, 10 ins. diam., bears N.20°E., 125 lks. dist. mkd. T10SR38ES31SCBT.
A ponderosa pine, 7 ins. diam., bears N.1°W., 22 lks. dist. mkd. T10SR37ES36SCBT.
A larch 9 ins. diam., bears N.71 1/2°W., 102 1/2 lks. dist. mkd. T10SR37ES36SCBT.

Deposit basalt stone, 9x7x5 ins., mkd. X, alongside iron post.

Description of corner evidence found:

Found a 2 1/2" BLM brass cap, 4" out of the ground, with a stone mound to the cap, marked as per diagram.

From which:

A pine, 8" in diam., bears N.1°E., 14.1 ft., with healed blaze.
A tamarack, 21" in diam., bears N.20°E., 81.8 ft., with healed blaze.
A tamarack, 15" in diam., bears N.50°E., 38.1 ft., with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

A pine, 20" in diam., bears S.67°E., 10.0 ft., double blazed and scribed, "XBT" with nail and brass washer "RLS 1060" in face of BT.

Place a post with Forest Service Sign (54-9) alongside corner.

Placed Forest Service signs (54-2, 54-9) on trees and paint scars, blazes, and 6" red band around all BT's.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/98

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

Z-1

FILED May 29, 1998
BAKER COUNTY SURVEYOR
SURVEY NO. 10-37-123
10-38-148