

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T10S R38E

## DIAGRAM

S C

T 10 S R 37 E [sic]  
¼ S 31

1971

### History of original corner establishment:

Eugene P. McCormack, U.S. Deputy Surveyor  
July 27, 1881

40.00 Set a post 4 ft. long, 4 ins. square, 24 ins in the ground for standard ¼ sec. cor.  
mark SC¼S on N. From which:

A pine, 7 ins. diam., bears N.40°E., 10 lks. dist. mkd. SC¼SBT.  
A fir, 30 ins. diam., bears South, 6 lks. dist. mkd. SC¼SBT.

Owen C. Chatters II and James J. Carlson, Cadastral Surveyors  
June 13, 1977

The standard ¼ cor. of sec. 31, determined at record distance from the original bearing trees:

A pine stump, 12 ins. diam., bears N.40°E., 10 lks. dist., with scribe marks BT visible on open blaze.  
A fir stump, 32 ins. diam., bears South, 6 lks. dist., no marks visible.

### At the corner point:

Set an iron post, 28 ins. long, 2 ½ ins. diam., 24 ins. in the ground, with brass cap,  
from which new bearing trees:

A ponderosa pine, 10 ins. diam., bears N.35°E., 98 lks. dist. mkd. ¼S31SCBT.  
A ponderosa pine, 11 ins. diam., bears N.40°W., 83 lks. dist. mkd. ¼S31SCBT.

Deposit basalt stone 9x7x4 ins., mkd. X, alongside iron post.

### Description of corner evidence found:

Found a 2½" BLM brass cap, 2" out of the ground, with a stone mound to the cap, marked as per diagram.

From which:

A pine, 14" in diam., bears N.40°W., 54.2 ft., with healed blaze.

### Description of monument and accessories I established to perpetuate the original location of this corner:

A fir, 12" in diam., bears N.71°E., 31.0 ft., double blazed and scribed, "SC¼S31BT" with nail and brass washer "RLS 1060" in face of BT.  
A pine, 12" in diam., bears S.50°W., 16.2 ft., double blazed and scribed, "EG+BHBT" with nail and brass washer "RLS 1060" in face of BT.  
A pine, 8" in diam., bears N.75°W., 12.8 ft., double blazed and scribed, "XBT" with nail and brass washer "RLS 1060" in face of BT.

Placed Forest Service signs (54-2,54-9) on trees and paint scars, blazes and a 6" red band around BT's.  
Place a post with Forest Service Sign (54-9) alongside corner.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*R. David Schurian 2/98*

OREGON  
JUNE 18, 1976  
R. DAVID SCHURIAN  
1060

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was filed in this office  
for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
\_\_\_\_\_ by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)

FILED May 29, 1998  
BAKER COUNTY SURVEYOR  
SURVEY NO. 10-37-124