

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a post 3 ft. long, 3 ins square 24 ins in the ground, for 1/4 sec. cor., marked 1/4S on N face, from which:

A pine 10 ins diam. bears N45°W, 22 lks dist, marked 1/4S BT.

A pine 48 ins diam. bears S15°W, 54 lks dist, marked 1/4S BT."

In 1971 the Bureau of Land Management monumented the corner as follows:

"The 1/4 sec. cor. of secs. 4 and 9, monumented with a mound of stone, 2 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A pine stump, 48 ins. diam., bears S15°W, 54 lks. dist., with scribe marks BT visible on open blaze.

At the corner point set an iron post 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd. as shown on diagram,

from which new bearing trees:

A ponderosa pine, 10 ins. diam., bears S43°W, 49 1/2 lks. dist., mkd. 1/4 S9 BT.

A western larch, 9 ins. diam., bears N28°W, 46 1/2 lks. dist., mkd 1/4 S4 BT.

Bury a granite stone, 9 x 6 x 4 ins., with an X chiseled on N. face, and deposit a brown glass bottle alongside iron post."

DIAGRAM

T10S R37E

S4

1/4

S9

1971
BLM

Description of corner evidence found:

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post set 4 ft. E, from which:

A 15" Ponderosa Pine bears S43°W, 49 1/2 lks. with blaze healed over.

A 12" Western Larch bears N28°W, 46 1/2 lks. with blaze healed over.

A 23" Ponderosa Pine bears N45°W, 22.2 ft. with blaze opened by others.

It appears that the 23" bearing tree is an original BT, but there seems to either be an error in the original field notes where 22 links should be 33 links or the corner stone was moved before the BLM found it. I lean towards the transcription error. For some reason the BLM 1971 notes do not include this tree as being found, but the tree has a BT tag that is dated 1960.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained corner by attaching "Land Survey Monument" signs to steel post and bearing trees as needed, painting 6" wide red bands around bearing trees, and making new accessories:

A silver DEEP (Underground Magnetic Locator) N43°E, 2.8 ft. from corner position, 1.2 ft. in ground.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 15, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-39

Baker County Surveyor

Client: Dick Haynes, Lyle Defrees & US Forest Service

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 9, 1985
LELAND LEE MYERS
699

Renewal Date 1/1/97

T10S R37E E-11