

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a post 4 ft long, 4 ins square 24 ins in the ground, for cor. to secs 3,4,9&10, marked T10S, S3 on NE, R37E, S10 on SE, S9 on SW and S4 on NW faces, with 5 notches on S and 3 notches on E edges, from which:

- A pine 12 ins diam. bears N35°E 67 lks dist, marked T10S R37E S3 BT.
- A pine 10 ins diam. bears S20°W, 115 lks dist, marked T10S R37E S9 BT."
- A pine 14 ins diam. bears N45°W, 83 lks dist, marked T10S R37E S4 BT.
- No other tree within limits and dug a pit 18 x 18 x 12 ins in Sec. 10.

**DIAGRAM**

T10S R37E

S4

S3

S9

S10

1971  
CS

In September, 1971, James Hanley monumented with a 1" galvanized pipe and 2½" aluminum cap under Survey No. 10-37-2, but set no accessories.

In July, 1982, Harry Hildebrand added accessories as follows:

"At the corner location I found the Aluminum cap set by James D. Hanley in 1971. I found no evidence of the original corner because it falls in the tailings left by the Sumpter dredging operations. From the aluminum cap set by James Hanley, I set three bearing trees:

- A 5" Lodge Pole Pine bears S32°E, 35.00 ft. marked X BT Nail in N. base.
- A 17" Ponderosa Pine bears N13°45'W, 71.50 ft. marked T10S R37E S4 BT Nail in N.E. base.
- A 17" Lodge Pole Pine bears S63°W, 83.10 ft. marked T10S R37E S9 BT Nail in S. base.

Bearings taken with a staff compass. Declination 18½°E. per 1980 Isogonic chart. Distances pulled to 60d nails with a brass washer marked L.S. 1898 set in side center of bearing trees."

**Description of corner evidence found:**

Found the James Hanley County Surveyor aluminum cap in good condition, stamped as shown on diagram, with steel post set 1 ft. S, from which:

- An 8" Lodgepole Pine bears S32°E, 35.00 ft., with scribing still visible.
- A 23" Lodgepole Pine bears S63°W, 83.10 ft., with scribing still visible.
- A 18" Ponderosa Pine bears N13°45'W, 71.50 ft., with scribing still visible.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Maintained corner by painting 6" wide red bands around the bearing trees, and making a tie to a 1" galvanized pipe with an aluminum cap set by PLS 645 in 1969 as the section corner in Survey No. 10-37-01. This position has not been accepted as explained in Survey No. 10-37-02. This reference monument bears S88°30'E, 63.45 feet from the Hanley monument.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 15, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-40

**Baker County Surveyor**

Client: Dick Haynes, Lyle Defrees & US Forest Service

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 9, 1985  
LELAND LEE MYERS  
699

Renewal Date 1/1/97

T10S R37E E-13