

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a post 3 ft. long, 3 ins square 24 ins in the ground, for 1/4 sec. cor., marked 1/4S on N face, from which:

A Pine 18 ins diam. bears N40°W, 100 lks dist, marked 1/4S BT.

A Pine 20 ins diam. bears S5°W, 78 lks dist, marked 1/4S BT."

Corner was re-established by Jame Hanley, RPE 2808, by single proportionate measurement during a dependent resurvey dated April, 1975.

Baker County Map of Survey No. 10-37-7 shows a 1/2" rebar was set for the corner on the edge of the highway with 2 reference monuments set on the section line near or on the right-of-way line. The record distances to the 1" galvanized pipe with 2" aluminum cap reference monuments are 64.66 feet easterly and 104.50 feet westerly.

Map of Survey No. 10-37-23 by William Hanley, PLS 1639, dated October, 1982, shows the corner point to be marked with a RR spike.

**DIAGRAM**

T10S R37E

S3

1/4

S10

1975

**Description of corner evidence found:**

Found the railroad spike in the pavement and the two reference monuments as stated above. The corner location is within the dredge tailings area and the roadway of Oregon State Highway No. 7, so all evidence of the original corner is gone.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Additional references tied to the RR spike are:

A 4x4 post with a Railroad Crossing Sign bears N35°W, 41.1 feet

A 4x4 post with a Curve Right Arrow Sign bears S30°W, 91.4 feet

There are no trees within acceptable limits.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on July 14, 1994, I maintained the corner as herein described.

**FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS**

**7 DAY OF Feb, 1995.**

10-37-41

**Baker County Surveyor**

Client: Dick Haynes, Lyle Defrees & US Forest Service

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 9, 1986  
LELAND LEE MYERS  
699

Renewal Date 1/1/97

**T10S R37E E-15**