

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a post 3 ft. long, 3 ins square 24 ins in the ground, for 1/4 sec. cor., marked 1/4S on W. face, from which

A pine 28 ins diam. bears N15°E, 62 lks. dist., marked 1/4 S BT.

A pine 30 ins diam. bears N50°W, 48 lks. dist., marked 1/4 S BT."

DIAGRAM

T10S R37E

1/4

S9 | S10

1994

PLS699

Description of corner evidence found:

Found a large spike in the ground which has been used as the quarter corner by others. After checking the relative location with other corners, accepted the spike as the best evidence of the corner position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2" galvanized pipe with 2 1/2" brass cap, stamped as shown in diagram, 28" in ground, from existing evidence, from which new accessories are:

An 11" Ponderosa Pine, bears S10°30'E, 15.80 ft., scribed "1/4 S10 BT"

A 9" Ponderosa Pine, bears S72°30'W, 23.84 ft., scribed "1/4 S9 BT"

A blue DEEP (Underground Magnetic Locator), bears N10°30'W, 3.4 ft. from corner position, 0.5 ft. in ground.

A pink DEEP, bears N72°30'E, 2.70 ft. from corner position, 0.5 ft. in ground.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 16, 1994, I monumented the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-48

Baker County Surveyor

Client: Dick Haynes, Lyle Defrees & US Forest Service

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 9, 1986
LELAND LEE MYERS
699**

Renewal Date 1/1/97

T10S R37E G-13