

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously set.

DIAGRAM

T10S R37E

S 1/16

S8 | S9

1994

PLS699

Description of corner evidence found:

Corner is being set by this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2" aluminum pipe with 3 1/4" aluminum cap, stamped as shown in diagram, 26" in ground, at a point as determined by the procedures set forth in the MANUAL OF INSTRUCTIONS FOR THE SURVEY OF PUBLIC LANDS for the subdivision of sections, in mound of earth and rock 30" base, 4" high, from which new accessories are:

A 9" Douglas Fir, bears N3°35'E, 5.05 ft., scribed "S1/16 S8 BT"

An 8" Lodgepole Pine, bears N61°55'W, 19.21 ft., scribed "S1/16 S9 BT"

Also set galvanized steel posts with "Property Boundary" and "Land Survey Monument" sign 3 ft. N. and "Property Boundary" sign 4 ft. E..

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 14, 1994, I monumented the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-52

Baker County Surveyor

Client: US Forest Service

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Leland Lee Myers
OREGON
JULY 9, 1986
LELAND LEE MYERS
699

Renewal Date 1/1/97

T10S R37E H-9