

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a basalt stone 13 x 11 x 8 ins 9 ins in the ground, for cor. to secs 8,9,16&17, marked with 4 notches on S and E edges, from which:
A pine 18 ins diam. bears N45°E 47 lks dist, marked T10S R37E S9 BT.
A pine 30 ins diam. bears S65°E, 100 lks dist, marked T10S R37E S16 BT.
A pine 10 ins diam. bears S15°W, 38 lks dist, marked T10S R37E S17 BT.
A pine 22 ins diam. bears N30°W, 29 lks dist, marked T10S R37E S8 BT."

In 1971 the Bureau of Land Management monumented the corner as follows:

"The cor. of secs. 8, 9, 16 and 17, monumented with the original basalt stone, 10 x 6 x 5, firmly set 6 ins. in the ground, mkd. with faint chisel marks on S. and E. faces, from which the remains of the original bearing trees:
A pine, 18 ins. diam., bears N45°E, 47 lks. dist., with scribe marks T10S R37E S9 BT visible on open face.
A pine stump, 30 ins. diam., bears S65°E, 100 lks. dist., no marks visible on partial blaze.
A pine stump, 12 ins. diam., bears S15°W, 38 lks. dist., no marks visible on partial blaze.
At the corner point set an iron post 28 ins. long, 2 1/2 ins, diam., 24 ins. in the ground, with brass cap mkd. as shown on diagram,

from which new bearing trees:
A fir, 6 ins. diam., bears N42°E, 27 lks. dist., mkd. T10S R37E S9 BT.
A ponderosa pine, 7 ins. diam., bears S72°E, 80 lks. dist., mkd. T10S R37E S16 BT.
A ponderosa pine, 9 ins. diam., bears S35°W, 97 lks. dist., mkd. T10S R37E S17 BT.
A ponderosa pine, 16 ins. diam., bears N85°W, 34 lks. dist., mkd T10S R37E S8 BT.
Bury corner stone, to which I add an X chiseled on W. face, alongside iron post and raise a mound of stone 2 ft. base, 1 1/2 ft. high, W of the corner."

Description of corner evidence found:

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post set 5 ft. W, from which:

- A 9" Ponderosa Pine bears S72°E, 80 lks., with blaze healed over.
- A 23" Ponderosa Pine bears S15°W, 28 ft., with blaze healed over.
- A 11" Ponderosa Pine bears S35°W, 97 lks., with blaze healed over.
- A 18" Ponderosa Pine bears N85°W, 34 lks., with scribing still visible.
- A 10" Douglas Fir bears N42°E, 27 lks., with blaze healed over.

DIAGRAM

T10S R37E

S 8 | S 9

S17 | S16

1971
BLM

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained corner by attaching "Land Survey Monument" signs to steel post and bearing trees as needed, and painting 6" wide red bands around bearing trees.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 15, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS
7 DAY OF Feb, 1995.

10-37-56

Baker County Surveyor

Client: US Forest Service

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 9, 1985
LELAND LEE MYERS
699

Renewal Date 1/1/97

T10S R37E J-9