

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a basalt stone 24x13x10 ins, 18 ins in the ground, for cor. to secs 9,10,15&16, marked with 4 notches on S and 3 notches on E edges, from which:  
A pine 24 ins diam. bears N85°E 134 lks dist, marked T10S R37E S10 BT.  
A pine 24 ins diam. bears S50°E, 155 lks dist, marked T10S R37E S15 BT."  
A pine 24 ins diam. bears S35°W, 136 lks dist, marked T10S R37E S16 BT."  
A pine 20 ins diam. bears N50°W, 150 lks dist, marked T10S R37E S9 BT.

**DIAGRAM**

T10S R37E

S9 | S10

S16 | S15

1971  
BLM

In 1971 the Bureau of Land Management monumented the corner as follows:

"The cor. of secs. 9, 10, 15 and 16, monumented with the original basalt stone, 24 x 14 x 7, firmly set 10 ins. in the ground, mkd. with 4 grooves on S. face and 3 grooves on E. face, from which the remains of the original bearing trees:

A pine stump, 24 ins. diam., bears S89°E, 185 lks. dist., with scribe marks BT visible on open blaze.(Record, N85°E, 134 lks.)

A pine stump, 24 ins. diam., bears S48°E, 155 lks. dist., with no scribe or blaze marks visible.(Record, S50°E)

A pine stump, 24 ins. diam., bears S35°W, 236 lks. dist., no marks visible.(Record, 136 lks.)

A pine stump, 20 ins. diam., bears N54°W, 150 lks. dist., with scribe marks BT visible on open blaze.(Record, N50°W)

At the corner point set an iron post 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd. as shown on diagram,

from which new bearing trees:

A ponderosa pine, 11 ins. diam., bears N27°E, 59 1/2 lks. dist., mkd. T10S R37E S10 BT.

A ponderosa pine, 13 ins. diam., bears S11°E, 60 lks. dist., mkd. T10S R37E S15 BT.

A ponderosa pine, 9 ins. diam., bears S89°W, 33 lks. dist., mkd. T10S R37E S16 BT.

A ponderosa pine, 13 ins. diam., bears N8°W, 47 lks. dist., mkd T10S R37E S9 BT.

Bury corner stone alongside iron post."

**Description of corner evidence found:**

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post alongside, from which:

A 16" Ponderosa Pine bears S11°E, 60 lks., with scribing still visible.

A 12" Ponderosa Pine bears S89°W, 33 lks., with scribing still visible.

A 15" Ponderosa Pine bears N8°W, 47 lks., with scribing still visible.

A 13" Ponderosa Pine bears N27°E, 59½ lks., with blaze healed over.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Maintained corner by attaching "Land Survey Monument" signs to steel post and bearing trees as needed, and painting 6" wide red bands around bearing trees.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on June 15, 1994, I maintained the corner as herein described.


FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-59

**Baker County Surveyor**

Client: Lyle Defrees & US Forest Service



Renewal Date 1/1/97

**T10S R37E J-13**