

CERTIFIED RECORD OF LAND CORNER

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a basalt stone 14 x 10 x 10 ins 9 ins in the ground, for 1/4 sec. cor., marked 1/4S on N face, from which:

A Pine 8 ins diam. bears N20°E 64 lks dist, marked 1/4S BT.

A Pine 36 ins diam. bears S65°E, 7 lks dist, marked 1/4S BT."

In 1971 the Bureau of Land Management monumented the corner as follows:

"The 1/4 sec. cor. of secs. 23 and 26, monumented with the original basalt stone, 14 x 10 x 10, firmly set 5 ins. below the surface of the ground, mkd. 1/4 on N. face, from which the remains of the original bearing trees:

A root hole, bears S65°E, 7 lks. dist., with a down pine alongside, 38 ins. diam., no marks visible.

A root hole, bears N20°E, 64 lks. dist., with a down pine alongside, 16 ins. diam., no marks visible.

At the corner point set an iron post 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd. as shown on diagram,

from which new bearing trees:

A ponderosa pine, 16 ins. diam., bears S49°E, 30 1/2 lks. dist., mkd. 1/4 S26 BT.

A western larch, 7 ins. diam., bears N16°E, 87 1/2 lks. dist., mkd 1/4 S23BT.

Bury corner stone alongside iron post."

Description of corner evidence found:

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post set 5 ft. W., from which:

A 20" Ponderosa Pine bears S49°E, 30 1/2 lks. with blaze healed over.

A 9" Western Larch bears N16°E, 87 1/2 lks. with blaze healed over.

DIAGRAM

T10S R37E

S23

1/4

S26

1971

BLM

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained corner by attaching "Land Survey Monument" signs to steel post and bearing trees as needed, painting 6" wide red bands around bearing trees, and making new accessories:

An orange DEEP (Underground Magnetic Locator) N49°W, 2.5 ft. from corner position, 1.3 ft. in ground.

A blue DEEP S16°W, 2.6 ft. from corner position, 1.3 ft. in ground.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on November 19, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS

7 DAY OF Feb, 1995.

10-37-63

Baker County Surveyor

Client: Lyle Defrees & US Forest Service



Renewal Date 1/1/97

T10S R37E R-19