

CERTIFIED RECORD OF LAND CORNER

History of original corner establishment:

Corner was established by William R. Gradon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.  
"Set a basalt stone 18 x 12 x 10, 12 ins in the ground, for cor. to secs 23,24,25&26, marked with 2 notches on S and 1 notch on E edges, from which:  
A pine 14 ins diam. bears N40°E 62 lks dist, marked T10S R37E S24 BT.  
A pine 14 ins diam. bears S65°E, 28 lks dist, marked T10S R37E S25 BT.  
A pine 16 ins diam. bears S50°W, 4 lks dist, marked T10S R37E S26 BT.  
A pine 26 ins diam. bears N55°W, 41 lks dist, marked T10S R37E S23 BT."

In 1971 the Bureau of Land Management monumented the corner as follows:

"The cor. of secs. 23, 24, 25 and 26, monumented with the original conglomerate stone, (record, basalt), 18 x 12 x 10 ins., firmly set 14 ins. in the ground, mkd. with 2 grooves on S. face, and 1 groove on E. face, from which the remains of the original bearing trees:

- A pine stump, 16 ins. diam., bears N40°E, 62 lks. dist., with scribe marks S24 BT visible on open blaze.
- A pine , 24 ins. diam., bears S65°E, 32 lks. dist., with scribe marks T10S R37E S25 BT visible on open blaze.(Record, 28 lks.)
- A pine stump, 18 ins. diam., bears S45°W, 4 lks. dist., with scribe marks T10S R37E S26 BT visible on open blaze.(Record, S50°W)
- A pine stump, size indeterminate, bears N55°W, 41 lks. dist., no marks visible.
- At the corner point set an iron post 28 ins. long, 2 1/2 ins, diam., 24 ins. in the ground, with brass cap mkd. as shown on diagram,
- from which new bearing trees:
- A western larch, 11 ins. diam., bears N47°E, 102 lks. dist., mkd. T10S R37E S24 BT.
- A ponderosa pine, 11 ins. diam., bears S35°E, 74 1/2 lks. dist., mkd. T10S R37E S25 BT.
- A ponderosa pine, 7 ins. diam., bears S49°W, 35 lks. dist., mkd. T10S R37E S26 BT.
- A ponderosa pine, 8 ins. diam., bears N79°W, 67 lks. dist., mkd T10S R37E S23 BT.
- Bury corner stone alongside iron post, and raise a mound of stone, 2 ft. base, 1 1/2 ft. high, West of the corner."

Description of corner evidence found:

Found 1971 BLM brass cap in good condition, stamped as shown on diagram, with steel post set alongside, from which:

- A 9" Ponderosa Pine, bears S49°W, 35 lks., with blaze still visible.
- A 10" Ponderosa Pine, bears N79°W, 67 lks., with blaze still visible.
- A 16" Western Larch, bears N47°E, 102 lks., with blaze healed over.
- A 15" Ponderosa Pine, bears S35°E, 74 1/2 lks., with blaze healed over.
- A 27" Ponderosa Pine, bears S65°E, 28 lks., with blaze still visible.
- A 13" stump, 5 ft. high, bears S50°W, 2.5 ft., with blaze still visible.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained corner by attaching "Land Survey Monument" signs to steel post and bearing trees as needed, and painting 6" wide red bands around bearing trees.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on November 19, 1994, I maintained the corner as herein described.

FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS  
7 DAY OF Feb, 1995.

10-37-64

Baker County Surveyor

Client: Lyle Defrees & US Forest Service

DIAGRAM

T10S R37E

S23 S24

S26 S25

1971  
BLM



Renewal Date 1/1/97

T10S R37E R-21